

To: 1 090172 3-9
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,490-0000 21
S/2 NE SW, SEC. 29, T. 29, S, R. 22 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 N. Market, Suite 205
Wichita, KS 67202

1650 feet from S section line

3300 feet from E section line

Lease Name Scheufler Well # D-1

County Ford 177.12

Well Total Depth 5450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 497

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530-0768

Company to plug at: Hour: 11:30 a.m. Day: 9 Month: 3 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

work: 4 1/2" at 5420' w/150 sx cement, PBD 5387', Perfs at 5276-78, 5280-82'

1st plug sand back to 5200' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1992 3-13-92

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 9 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 5200' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3032' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (operator) observe this plugging.

DATE 3-17-92

INV. NO. 36773

Signed [Signature] (TECHNICIAN) RAY