

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-097-20032-0000

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 9-6-67 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TGT Petroleum Corp. OPERATORS LICENSE NO. 5118

ADDRESS 209 E. William - Wichita, Ks. 67202 PHONE # (316) 262-6489

LEASE (FARM) Pyle-Taylor WELL NO. 1 WELL LOCATION N/2 SW/4 COUNTY Kiowa

SEC. 1 TWP. 28S RGE. 19 (~~EX~~(W)) TOTAL DEPTH 4857 PLUG BACK TD 1190

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 378 CEMENTED WITH 250 SACKS

CASING SIZE 4 1/2" SET AT 4856 CEMENTED WITH 200 SACKS

PERFORATED AT 4849'-51', 4840'-44', 4828'-34', 4410'-14'

CONDITION OF WELL: GOOD POOR Collapsed pipe CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL See back of form

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not avail. IS ACO-1 FILED?
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:00 AM August 26, 1985 - Monday

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mark Danner PHONE # (316) 463-3524

ADDRESS Burrton, Ks.

PLUGGING CONTRACTOR TGT Petroleum Corp. LICENSE NO. 5118

ADDRESS Wichita, Ks. PHONE # (316) 262-6489

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: B. Lynn Herrington
(Operator or Agent)
B. Lynn Herrington, Ex. Vice Pres.

RECEIVED
AUG 23 1985

DATE: Aug. 22, 1985

CONSERVATION DIVISION
Wichita, Kansas

8-23-1985

①

This well has collapsed pipe at 3000'. Prior to the casing collapsing, we set a cast iron bridge plug @ 4105'. We then set another cast iron bridge plug @ 1500', and perforated the Anhydrite @ 1210'-12'. We then pumped 250 sx. of cement, followed by wiper plug to 1190'. We then ran a temp. survey and found top of cement @ 580'. We then perforated from 575' to 577' and pumped 150 sx. of cement and circulated cement to surface behind pipe.

We now propose to plug this well by spotting a 20 sx. plug @ 750', followed by 4 sx. gel, then pull up to 90' and set an 8 sx. plug to surface of pipe.



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
LEITH R. HENLEY
UDITH A. MCCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

NOV 23 1985

EXPIRES

August 23, 1985

WELL PLUGGING NOTICE

Pyle-Taylor #1
100'W C N/2 SW/4
Sec. 1-28S-19W
Kiowa County

TGT Petroleum Corp.
209 E. William
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).