

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- OWWO

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Banks Oil Co.

Complete Address 200W Douglas #500 Wichita Kansas 67202

Lease Name Ratzloff Well No. 1

Location 660' ENL - 660' FWL Sec. 34 Twp. 29 Rge 25 (East) (West)

County Lord Total Depth 5357'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc.

Address Box 847, Pratt Kans 67124 License No. 761

Operation Completed: Hour: 3:30 PM Day: 8 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5357' of 4 1/2" production pipe & plugged back to 5330'. The cement outside 4 1/2" was at 4735'. The perforations were from 5259' to 69'. 1st plug sanded off bottom. To 5200' put 4 bbl of cement on sand with halor. 2nd plug at 425' with 50 bbl of cement pumped through 4 1/2". 3rd plug on solid bridge at 40' to 0' with 10 bbl of cement. Then filled rat hole with 10 bbl of cement. They recovered 278' of 4 1/2" pipe. The plugging was accomplished by Allied Cementing

Amount of Surface Casing: 379' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was at Pirt meeting at Great Bend, Kans.

Signed: Paul A. Luthis
Conservation Division Agent

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 6-15-82

JUN 15 1982
6-15-1982

INV. NO. 432-u

CONSERVATION DIVISION
Wichita Kansas