

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 1 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wynn of Gabbert & Jones, Inc has this  
date requested permission to plug the following described well:

Mr. Wynn guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co

Complete Address: 780 4th Natl Bldg Wichita, KS

Lease Name: Dean A Well No. 1

Location: 100' W of C SW/NE Sec. 35 Twp. 29S Rge 20 (E)(W)W

County: Kiowa Total Depth 5195 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wynn was instructed to plug the well as follows:

647 ft 8 5/8 surface cemented with 500 sacks. Pump plug,  
40 sacks cement to 400 ft. Mud to 40 ft, plug, 1/2 sack  
hulls, 15 sacks cement to surface. 2 sacks cement in  
rat hole.

Pumped by Halliburton Cementing Co Great Bend, KS

Very truly yours,

*[Signature]*  
Conservation Division Agent