



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION (Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 14, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-057-~~68~~-20-242-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1981

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Doyle Holters of Lee Banks Co.

has this

9-17-1981

date requested permission to plug the following described well:

Operator's Full Name: D. R. Louch Oil Co. Inc.

Complete Address: 221 Broadway, Suite 400, Wichita, Kansas 67202

Lease Name: Koppes Well No. 1

Location: C-SE NE Sec. 26 Twp. 29S Rge. 25W (E) (W)

County: Ford Total Depth: 5400

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Holters was instructed to plug the well as follows:

There is 613' of 8 5/8" surface casing. Cement circulated, the
Merita was topped 350 to 400' so its behind surface casing. 1st plug
with hole full of heavy mud, pushed rubber plug to 585' and put
40 sks of cement on top of rubber plug. 2nd plug from 40' to 0' with sks
of shells + 10 sks of cement on top of solid bridge at 40'. Then they put 10 sks
of cement in the rat hole. There wasn't any mouse hole drilled.
Plugging accomplished by Allied Cementing Co. Great Bend Mo,
Very truly yours,

Paul Luther
Conservation Division Agent