

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

6-7-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

150WNO

Dear Sir:

Mr. Lee Banks of Banks Oil Co has this date requested permission to plug the following described well:

Operator's Full Name: Banks Oil Co.

Complete Address: 200 W. Douglas #500 Wichita, Kansas 67202

Lease Name: Ratzloff Well No. 1

Location: 660' ENL - 660' FWL Sec. 34 Twp. 29 Rge. 25 (E) (W)

County: Ford Total Depth: 5357'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Banks was instructed to plug the well as follows:

They ran 5357' of 4 1/2" production pipe & plugged back to 5330'
The cement outside of 4 1/2" top was at 4735'. The Perforations
were from 5259' to 69'. 1st plug sandbed bottom back to
5200' & dumped 4 bbls of cement on top of sand with bailer. 2nd
plug at 425' with 50 bbls of cement. 3rd plug 40' too on solid
bridge with 10 bbls of cement. Then filled rat hole with 10 bbls
of cement. (over)

Very truly yours,

Paul A. Luthie
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1982

CONSERVATION DIVISION
Wichita, Kansas
6-15-1982

They recovered "of 4 1/2" production type. The
plugging was accomplished by allied Cementing.

Faul Luttie