

2-8

1 070786

API NUMBER 15- 057-20,478-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NE NW, SEC. 17, T 29 S, R 22 (W/E)  
4420 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171  
Operator: TXO Production Corp.  
Name & Address: 1660 Lincoln Center, #1800  
Denver, CO 80264

Lease Name Seibel Well # A-1  
County Ford 177.13  
Well Total Depth 5450 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling License Number 5380

Address 2759 South Broadway, Wichita, KS 67216

Company to plug at: Hour: 8 p.m. Day: 8 Month: 2 Year: 19 90

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-945-9935  
Elevation 2498'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1491-1522'

1st plug at 1530' with 50 sx cement, 2nd plug at 1000' with 40 sx cement,

3rd plug at 550' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 8 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,

2nd plug at 1000' with 40 sx cement,

3rd plug at 550' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement, Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
FEB 14 1990

(did not) observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

INV. NO. 27434

2-8

EFFECTIVE DATE: 1-17-90

FORM MUST BE TYPED  
FORM C-1 12/85

State of Kansas <sup>15-</sup> 057-20,478-0000  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 2 1 1990 App SW NE NW Sec 17 Twp 29 S, Rg 22 X East  
month day year

~~5520~~ 4420 feet from South line of Section  
~~3600~~ 3670 feet from East line of Section  
(Note: Locate well on Section Plat Below)

OPERATOR: License # 5171  
Name: TXO Production Corp.  
Address: 1660 Lincoln Center, #1800  
City/State/Zip: Denver, CO 80264  
Contact Person: Cory West  
Phone: (303) 861-4246

County: Ford  
Lease Name: Seibel Well #: A-1  
Field Name: Unkn

CONTRACTOR: License #: 5380  
Name: Eagle Drilling

Is this a Prorated Field? Morrow yes X no

Well Drilled For: Well Class: Type Equipment:  
... Oil ... Inj ... Infield X Mud Rotary  
X Gas ... Storage X Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

Nearest lease or unit boundary: To Be Determined  
Ground Surface Elevation: To Be Determined feet MSL

Domestic well within 330 feet: ... yes X no

Municipal well within one mile: ... yes X no

Depth to bottom of fresh water: 100' 200'

Depth to bottom of usable water: 200' 480'

Surface Pipe by Alternate: X 1 ... 2

Length of Surface Pipe Planned to be set: 500

Length of Conductor pipe required: To Be Determined

Projected Total Depth: 5450

Formation at Total Depth: Morrow

Water Source for Drilling Operations:  
... well ... farm pond X other

If OWMO: old well information as follows:  
Operator: .....  
Well Name: .....  
Comp. Date: ..... Old Total Depth .....

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location: .....

500' Alt. I Req.

Exp. 6/12/90

AFFIDAVIT

PUSHER Outch Steiner  
TD 5450' FORMATION Miss.  
SURFACE PIPE 8 7/8" @ 526'  
ANHYDRITE 1491' ELEVATION 2498'  
STARTING TIME & DATE 8:00p 2-8-90  
COMPLETION TIME & DATE 11:00p 2-8-90  
1st PLUG @ 1530 FT. WI 50 SX  
2nd PLUG @ 1000 FT. WI 40 SX  
3rd PLUG @ 550 FT. WI 40 SX  
4th PLUG @ 40 FT. WI 10 SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI 10 SX  
WATER WELL PLUGGED WI 10 SX  
CEMENT COMPANY BJ Titan  
TECHNICIAN P.G.  
TYPE OF CEMENT 60/40 670

SPUD  
1-21-90  
500 1-8 7/8"  
yes w/w

5280	1850
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

RECEIVED  
STATE COMMISSION  
FEB 13 1990

Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.