

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-057 20,322-0000

N/2 NESW, Sec. 16, T 29 S, R 22 W/E

2300 feet from ~~W/S~~ section line

TECHNICIAN'S PLUGGING REPORT

2200 feet from W/E section line

Operator License # 7381

Lease Name Waldo A. Stimpert Well # 1

Operator: Mitchell Energy Corporation  
Name & Address: P.O. Box 4000  
Woodlands Texas  
77380

County Ford

Well Total Depth 5500 feet \$178.75

Conductor Pipe: Size 16" feet 60'

Surface Casing: Size 8 5/8" feet 618

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling, Inc License Number 5380

Address P.O. Box 8609 Wichita, Kansas. 67208

Company to plug at: Hour: 1:00pm Day: 15 Month: June Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Rick Wilson

(company name) Mitchell Energy Corporation (phone) \_\_\_\_\_

were: To use 60/40 pozmix 2% gel 3% cc  
1st Plug @ 1440' w/50sx, 2nd Plug @ 960'  
w/50sx 3rd Plug @ 660' w/40sx, 4th plug  
@ 40' w/solid Bridge Plug + 10sx. Circulate  
10sx each in both the rat hole + mousehole,

Signed Richard W. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:30pm Day: 15 Month: June Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph  
Mr. Paul Luthi gave plugging orders +  
witnessed part of the plugging  
Powell did the cement work

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Richard W. Lacy  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED  
DATE 6-24-83  
INV. NO. 4668-W