

5-20

227 R

To: 1 051436
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,160-0000
C SE, SEC. 21, T. 29 S, R 21 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9526
Operator: Dean McLemore
Name & Address: 909 N. Cedar
Medicine Lodge, KS 67104

Lease Name Christopher Well # 1
County Ford 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 554

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number
Address P.O. Box 632, Greensburg, KS 67054

Company to plug at: Hour: 10 a.m. Day: 20 Month: 5 Year: 19 91

Plugging proposal received from Dean McLemore
(company name) Dean McLemore (phone) 316-886-5885

were: 4 1/2" at 5298' w/125 sx cement, Perfs at 5186-92'
1st plug sand over perfs and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and
175 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 1:45 p.m. Day: 20 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 5136' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and
175 sx cement.

Maximum pressure 250 psi and shut in 200 psi.

RECEIVED
6-4-1991
JUN 04 1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2751' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-12-91
INV. NO. 32089

Signed Richard M. Lacey
(TECHNICIAN)