

8-25-87

184 R

To: 1 050928
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,417-0000
SE SE SE, SEC. 35, T 29 S, R 24 WEX
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6033
Operator: Murfin Drilling Company
Name & Address: 250 North Water, Suite 300
Wichita, KS 67202

Lease Name Moore Well # 1-35
County Ford 177.94
Well Total Depth 5475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1100

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 25 Month: 8 Year: 19 87

Plugging proposal received from Bill Fulls
(company name) Kelso Casing Pulling (phone) 316-938-2474

were: 5 1/2" at 5472' PBTD 5430' Perfs at 5312-19'
1st plug sand back to 5260' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 25 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 5260' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 125 sx cement.
Paul Luthi saw part of this plugging, also.

Maximum pressure 600 psi and shut in 0 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1987
8-28-1987
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 9-2-87
INV. NO. 17984

Signed Richard W. Lacey (TECHNICIAN)