

1090229

API NUMBER 15- 057-20,381-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N/2 SE NW, SEC. 22 ; T 29 S, R 25 W/R  
3300 feet from ~~NX~~ section line  
3630 feet from ~~WX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7381

Lease Name B. Daniels Well # 1

Operator: Mitchell Energy Corporation

County Ford

Name & Address P. O. Box 4000

Well Total Depth 5276 171.47 feet

The Woodlands, TX 77380

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 646

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 6:00 pm Day: 25 Month: August Year: 19 84

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1500' with 50 sx cement

2nd plug at 1050' with 50 sx cement

3rd plug at 690' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by R.B. Farber (TECHNICIAN)

7th plug to circulate mouse hole with 10 sx cement

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 pm Day: 25 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 1050' with

50 sx cement, 3rd plug at 690' with 40 sx cement, 4th & 5th plugs - solid bridge -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. RECEIVED

STATE CORPORATION COMMISSION

SEP 17 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton CONSERVATION DIVISION

If additional description is necessary, use BACK of THIS FORM.

INVOICED

(check / do not) observe this plugging.

DATE 9-20-84

Signed R.B. Farber (TECHNICIAN)

INV. NO. 3785