

090959
TO: STATE CORPORATION COMMISSION

10-13

API NUMBER 15-057-20,298-~~6060~~
C SE SEC. 25, T 29 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 1990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 760 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MCCUNE "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY FORD 178.75

OPERATOR LICENSE # 5004 WELL TOTAL DEPTH 5500 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE 5 1/2 " FEET 5500

NAME AND ADDRESS 125 N MARKET, SUITE 1075 SURFACE CASING: SIZE 8 5/8" FEET 1233'

WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PLAINS INC LICENSE NUMBER 4072

ADDRESS PO BOX 346, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 2:15 PM DAY: 13 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM PAT LIVINGSTON

(COMPANY NAME) PLAINS INC (PHONE) 785-798-3995

WERE: PERFS AT 5295-5299 PBDT AT 5460

1ST PLUG SAND TO 5230' WITH 5 SX CEMENT ON TOP, SPOT PLUGS THROUGH CASING COMING OUT OF HOLE. LEAD WITH 10 GEL, SPOT 50 SX CEMENT AT 1256'. PULL TO 550', SPOT 40 SX CEMENT. TOP OFF WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 13 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 5230' WITH 5 SX CEMENT ON TOP. SPOT PLUGS THROUGH CASING COMING OUT OF HOLE. LEAD WITH 10 GEL, SPOT 50 SX CEMENT AT 1256'. PULL TO 550', SPOT 40 SX CEMENT TOP OFF WITH 10 SX CEMENT.

10-15-1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2418' OF 5 1/2" CASING. CASING WAS MADE UP VERY TIGHT. TOOK EXTRA TIME TO LAY DOWN CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

10-19-98
60129