

1010142

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,378 -0000  
C S/2  
SE SE, SEC. 33, T 29 S, R 25 W/X

TECHNICIAN'S PLUGGING REPORT

330 feet from W/S section line

660 feet from W/E section line

Operator License # 5171

Lease Name Harris "P" Well # 1

Operator: TXO Production Corp.

County Ford

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5400 175.50 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 591

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Freeman Drilling, Inc. License Number 5106

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 3 Month: June Year: 19 84

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-862-5961

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1500' with 50 sx cement,

2nd plug at 850' with 50 sx cement

3rd plug at 620' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. Plugging Proposal Received by \_\_\_\_\_

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:30 pm Day: 3 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1500' with 50 sx cement, 2nd plug at 850' with 50

sx cement, 3rd plug at 620' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form)

(If conditions) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 05 1984

CONSERVATION DIVISION  
Wichita, Kansas

Signed Kenneth Beahm  
(TECHNICIAN)

**INVOICED**

DATE 6-15-84

INV. NO. 2046 6-3 JUL 1 7 1984