

1060184

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2 SE NW , SEC. 34 , T 29 S, R 25 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,370-0000

S/2 SE NW , SEC. 34 , T 29 S, R 25 W/E

2310 feet from N/E section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Wyatt "A" Well # 3

Operator: TXO Production Corp.

County Ford

Name & Address 200 West Douglas, Suite 300

Well Total Depth 5440.176.80 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 602

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Wichita, KS 67202

Company to plug at: Hour: 9:00 pm Day: 22 Month: February Year: 19 84

Plugging proposal received from E. J. Woody

(company name) H-30 Drilling, Inc. (phone) 316-672-3443

were: to fill hole full of heavy mud and spot cement through drill pipe.

1st plug at 1220' with 50 sx cement

2nd plug at 650' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:45 pm Day: 22 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1220' with 50 sx cement, 2nd plug at 650' with

50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to

circulate mousehole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

FEB 29 1984

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

(do not) observe this plugging.

DATE 3-8-84

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 0543