

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20 361-0000

SE/4, Sec. 34, T 29 S, R 25 W

1980 feet from ~~X~~/S section line

1980 feet from ~~X~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5731

Lease Name OSHLO Well # 1-34

Operator: THUNDERBIRD Drilling Inc County FORD

Name & Address P.O. Box 18407
Wichita, KS 67218

Well Total Depth 5700 feet 175.50

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 641

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor COMPANY TOOLS License Number _____

Address _____

Company to plug at: Hour: 9 AM Day: 15 Month: Jan Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) T-BIRD (phone) _____

were: to use 60/40 Pozmix, w/2% ogel - 3% CC AND SPOT THE
1st plug @ 1560' w/50 sy - 2nd plug @ 1020' w/50 sy
3rd plug @ 690' w/40 sy - 4th plug @ 40' w/solid
bridge of hells, wiper plug and 10 sy. Circulate
15 sy in the rat hole.

Signed R. Barbutan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 AM Day: 15 Month: JAN Year: 1984

ACTUAL PLUGGING REPORT Plugged as ordered. All plugs
set in heavy mud, spotted through
drill pipe. Cementing by Allied - Ticket
191912.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (~~was~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

Signed R. Barbutan
(TECHNICIAN)

DATE 1-20-84

INV. NO. 9219 W

FORM CP-2/3
Rev. 9-82