

To: 1 051219
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation
Name & Address 1660 Lincoln Street, Suite 1800
Denver, CO 80264

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 17 Month: 10 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5399' PBD 5386' Perfs at 5289-98'

1st plug sand back to 5150' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

_____ Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 17 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 5150' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 10-24-89

INV. NO. 26203

10-17

API NUMBER 15- 057-20,369 - 0000
NW SW SW, SEC. 34, T 29 S, R 25 W/E
990 feet from S section line
4950 feet from E section line
Lease Name Wyatt "A" Well # 2
County Ford 175.50
Well Total Depth 5400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 601

STATE CORPORATION COMMISSION

NOV 19 1989 10-19-1989

CONSERVATION DIVISION

Signed Richard W. Lacey
(TECHNICIAN)