

5-2

To: 1 051295
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20.333-0000
SW NE SW, SEC. 34, T 29 S, R 25 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152
Operator: Lee Banks Oil
Name & Address 200 West Douglas, Suite 550
Wichita, KS 67202

Lease Name Wyatt Well # 1-34
County Ford 176.67
Well Total Depth 5436 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 2 Month: 5 Year: 19 90

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 5434' Perfs at 5300-07'

1st plug pump 2 sx hulls and 20 sx cement to 5200',

Spot through casing: 2nd plug at 1550' with 50 sx cement,

3rd plug at 620' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 2 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 5200',

Spot through casing:
2nd plug at 1550' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Midwest Casing. Recovered 2600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(1) ~~XXXXXXXX~~ observe this plugging.

DATE 5-16-90

INV. NO. 28149
5-2

RECEIVED
MAY 09 1990
CONSTRUCTION DIVISION
WICHITA, KANSAS

Signed Richard M. Lacey
(TECHNICIAN)

5-9-1990