

1 051000

1-30-88

182  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,291-0000

C NE SE, SEC. 35, T 29 S, R 25 W/EX

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Fager Well # 2-J

Operator: Coastal Oil & Gas Corporation

County Ford 177.13

Name & Address 211 North Robinson, Suite 1700

Well Total Depth 5450 feet

Oklahoma City, OK 73102

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 632

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 30 Month: 1 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5437' PPTD 5396' Perfs at 5301-15'

1st plug set CIBP at 5200' with 2 sx cement on top,

2nd plug pump 40 sx cement at 1500', 3rd plug pump 50 sx cement at 950',

4th plug pump 35 sx cement at 660', 5th plug pump 10 sx cement at 40-10'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 30 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5200' with 2 sx cement on top - Dan Goodrow saw,

2nd plug pumped 40 sx cement at 1500',

3rd plug pumped 50 sx cement at 950',

4th plug pumped 35 sx cement at 660',

5th plug pumped 10 sx cement at 40-10'. Heavy mud between all plugs

RECEIVED  
STATE CORPORATION COMMISSION

FEB 03 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3227' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 2-4-88  
OBSERVE THIS PLUGGING.

Signed Richard M. Lacey (TECHNICIAN)

DATE 2-4-88

NO. 19716