

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-057-20,297-000 *R*

*E/2SWNE* Sec. 35, T 29 S, R 25 W *X*

660 feet from *X/S* section line

1650 feet from *X/E* section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name ASKEW Well # 2

Operator: COASTAL OIL & GAS  
Name & Address Box 1332  
AMARILLO, TX 79189

County FORD

Well Total Depth 1528 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 682'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling, Inc. License Number 5657

Address 200 Douglas Bldg, Wichita, KS 67202

Company to plug at: Hour: 5:00pm Day: 9 Month: JAN Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO LARRY FRIEDEL

(company name) Slawson (phone) \_\_\_\_\_

were: Use 50/50 Pozmix 4% gel-3% C.C., locate 1st plug @ 1020' w/50 st. cmt.; 2nd plug @ 690' w/40 st. cmt.; 3rd plug @ 40' w/solid bridge of 1/2 st. hulls & 8 5/8 plug, then 10 st. cmt. to surface. Rathole plugged w/10 st. circ.

Signed R. Barlett  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:00am Day: 9 Month: Jan Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered.  
Cementing by Halliburton.

Remarks: anhydrite tag @ 1528'

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 14 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed R. Barlett  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED  
DATE 2-10-83  
INV. NO. 2412-W