

1 090057

2-26

API NUMBER 15- 057-20,311 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NE, SEC. 35, T 29 S, R 25 W
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7105
Operator: Spines Exploration, Inc.
Name & Address: 224 E. Douglas, Suite 400
Wichita, KS 67202

Lease Name Askew Well # 3
County Ford 176.11
Well Total Depth 5419 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 650

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:40 p.m. Day: 26 Month: 2 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-5901

were: 5 1/2" at 5411' w/100 sx cement, Perfs at 5300-14'

1st plug set CIBP at 5200' and dump 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 p.m. Day: 26 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5200' and dump 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 175 sx cement.

Maximum pressure 520 psi and shut in 475 psi.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
FEB 28 1991

2-28-1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2548' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 3-11-91

INV. NO. 31095