

1 090056

2-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,255-0000
NW NE NE SEC. 35, T 29, S, R 25 W/E
4950 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7105
Operator: Spines Exploration, Inc.
Name & Address 224 E. Douglas, Suite 400
Wichita, KS 67202

Lease Name Askew Well # 1
County Ford 175.50
Well Total Depth 5400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 608

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:10 p.m. Day: 26 Month: 2 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-5901

were: 4 1/2" at 5399', Perfs at 5267-73'
1st plug set CIBP at 5200' and dump 2 sx cement on top,
2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 26 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5200' with 2 sx cement on top, (TECHNICIAN)

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 175 sx cement.

Maximum pressure 480 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2787' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-11-91

INV. NO. 31094

Signed _____ (TECHNICIAN)