

1 030728

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-057-20,415 - 0000  
N/2 NW NESEC. 36, T 29 S, R 25 W/E  
4950 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Cannon Well # 1-A

Operator: Pickrell Drilling Co., Inc.  
Name &  
Address 110 N. Market, Suite 205  
Wichita, Kansas 67202

County Ford 176.48  
Well Total Depth 5430 Mississippi feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Co., Inc. License Number 5123

Address 110 N. Market, Suite 205, Wichita, Kansas 67202

Company to plug at: Hour: 11:30 pm Day: 26 Month: July Year: 1986

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone) (316) 793-5742

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2577'  
Anhydrite 1580'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 700' with 50 sx cement

3rd plug at 30' below surface casing with 50 sx cement

4th plug CIBP at 40' with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:45 am Day: 27 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 1580' with 50 sx cement, 2nd plug at 700' with  
50 sx cement, 3rd plug at 540' with 50 sx cement, 4th plug from 40' to surface  
with 10 sx cement, and 5th plug to circulate rat hole with 15 sx cement.

RECEIVED

Remarks: Used 60/40 Pozmix with 6% gel pumped by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

AUG - 6 1986

DATE \_\_\_\_\_

AUG 5 1986

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 14615

8-5-1986