

ATd:

1 060627

API NUMBER 15- 057-20,366 - 0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE SE NE , SEC. 36 , T 29 S, R 25 (W) EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Oshlo Well # 1-36

Operator: Banks Oil Co.

County Ford 175.60

Name & Address P. O. Box 1884

Well Total Depth 5403 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 641

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 4:00 pm Day: 23 Month: July Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 5403', PBSD 5350' top of cement 4500' Perfs at 5293-97'

1st plug pump 1 sack hulls and 25 sx cement to bottom

Pump through 4 1/2" with mud between plugs  
2nd plug at 1500' with 50 sx cement

3rd plug at 670' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 6:00 pm Day: 23 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd plug at 1500' with 50 sx cement, 3rd plug at 670' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used Common Cement by Sargent's. Recovered 2800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE AUG 01 1985

JUL 26 1985

Signed Paul A. Luthi  
(TECHNICIAN)  
7-26-1985

INV. NO. 9247 7-23

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84