


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Gray County, Sec. 31 Twp. 29S Rge. 27 xR/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW NW
Lease Owner Pendleton Land & Exploration, Inc.
Lease Name Huelskamp Well No. #1
Office Address 1410 Security Life Bldg., Denver, Colorado 80202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed 11-7-79 19
Application for plugging filed 11-6-79 19
Application for plugging approved 11-6-79 19
Plugging commenced 11-6-79 19
Plugging completed 11-7-79 19
Reason for abandonment of well or producing formation
Commercial quantities of oil not found
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5450'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1651'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Plug @ 1600' w/50 sx.
- Plug @ 800' w/25 sx.
- Plug @ 40' w/10 sx.
- Rat Hole 5 sx.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1979
CONSERVATION DIVISION
WICHITA, KANSAS

11-29-1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 9 day of November, 1979
My commission expires _____
Sherry Herrell Notary Public

DRILLER'S LOG

COMPANY: Pendleton Land & Exploration, Inc.

SEC. 31 T. 29S R. 27W

WELL NAME: Huelskamp #1

LOC. NW SW NW

RIG NO. #2

COUNTY: Gray

TOTAL DEPTH 5450'

ELEVATION

COMMENCED: 10-22-79

COMPLETED: 11-7-79

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 1651' w/600 sx. Lite, 3% cc. and 150 sx. Class H, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)


Clay & Sand	315
Sand	700
Shale & Sand	1065
Shale	1090
Redbed	1619
Shale	2470
Shale & Lime	2510
Lime & Shale	3050
Shale & Lime	3190
Lime & Shale	4460
Lime	4570
Lime & Shale	5310
Lime	5450
<u>ROTARY TOTAL DEPTH</u>	<u>5450</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 29 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas)
 COUNTY OF Sedgwick) SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.
 upon oath state that the above and foregoing is a true and correct copy of the log of the
Huelskamp #1 well.

Wilson Rains
 Wilson Rains



Witnessed and sworn to before me this 9 day of November, 1979.

My Appointment Expires:
1-5-82

Sherry Ferrell
 Sherry Ferrell