

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. \_\_\_\_\_

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.


F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 8565 EXPIRATION DATE 6-30-84  
 OPERATOR HUEY P. GREY API NO. 15-097-20,953-0000  
 ADDRESS RR #1 BOX 47 COUNTY KIOWA  
GREENSBURG, KANSAS 67054 FIELD NICHOLS  
 \*\* CONTACT PERSON HUEY GREY PROD. FORMATION LANSING  
 PHONE (316) 723-3123  
 PURCHASER CLEAR CREEK, INC. LEASE GREY  
 ADDRESS P. O. BOX 1045 WELL NO. 3  
McPHERSON, KANSAS 67460 WELL LOCATION SE 1/4  
 DRILLING CONTRACTOR EAGLE DRILLING CO. 330 Ft. from South Line and  
990 Ft. from West Line of  
 ADDRESS P. O. BOX 8609 the SE (Qtr.) SEC 18 TWP 29 RGE 18 (W).  
WICHITA, KANSAS 67208

PLUGGING CONTRACTOR ADDRESS \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_



(Office Use Only)  
 KCC   
 KGS   
 SWD/REP \_\_\_\_\_  
 PLG. \_\_\_\_\_

TOTAL DEPTH 4900' PBD \_\_\_\_\_  
 SPUD DATE 3-27-84 DATE COMPLETED 4-5-84  
 ELEV: GR 2282 DF \_\_\_\_\_ KB 2295

DRILLED WITH (~~CABLE~~) (ROTARY) (~~AIR~~) TOOLS.  
 DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE \_\_\_\_\_

Amount of surface pipe set and cemented 441' DV Tool Used? \_\_\_\_\_

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other \_\_\_\_\_

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Frank Broadfoot, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Frank Broadfoot  
 (Name) Agent

SUBSCRIBED AND SWORN TO BEFORE ME this 5th day of May, 1984.



Helen Broadfoot  
 (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 3-10-87

\*\* The person who can be reached by phone regarding any questions concerning this information. RECEIVED STATE CORPORATION COMMISSION

MAY 4 1984

CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR HUEY P. GREY LEASE GREY SEC. 18 TWP. 29 RGE. 18 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 3

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.				
SAND, CLAY, <del>WELL</del>	380	380		
CLAY	380	445		
RED BED SHALE	445	800		
SHALE LIME	800	1950		
SHALE & LIME	1950	3560		
LIME & SHALE	3560	4360		
LIME	4360	4780		
LIME & SHALE	4780	4825		
RTD	4825			

If additional space is needed use Page 2, Side 2

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		8 5/8		441'	LITE 200 Class H 100	300	CIRC.
PRODUCTION		4 1/2		4825'	Thixotropic	250	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	Jumbo	4627-34

**TUBING RECORD**

Size	Setting depth	Packer set at
2 3/8	4690'	None

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
250 Gal. 15% HCl	4627-34

Date of first production April 5th, 1984	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity 45.5
Estimated Production -I.P. Oil 120 bbls.	Gas MCF	Water 25 % Gas-oil ratio bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Perforations