

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,448 ⁰⁰⁻⁰⁰

LEASE NAME Hakanson

WELL NUMBER 1-27

SPOT LOCATION C SW NE

SEC. 27 TWP. 29S RGE. 11 (W)

COUNTY Pratt

Date Well Completed 6-21-84

9:30 PM,

Plugging Commenced 6-21-84

10:45 PM,

Plugging Completed 6-21-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 2790'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	268'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud.
Heavy mud and 60 sacks at 960. Heavy mud and 40 sacks at 330.
Heavy mud, solid bridge, plug and 10 sacks at 40'. 15 sacks in
rathole, 10 sacks in mousehole. Used 60/40 Pozmix, 2% gel and 3% cc.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

JUN 26 1984

F. A. Wuellner (employee of operator) or CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Kansas
67579



SUBSCRIBED AND SWORN TO before me this 22 day of June, 19 84.

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - HAKANSON #1-27

Located: C SW NE, Section 27-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 18, 1984

COMPLETED: June 21, 1984

TOTAL DEPTH: 2790'

LOG

0 - 271 Sand and Clay
271 - 1570 Shale
1570 - 2708 Lime and Shale
2708 - 2744 - Indian Cave
2744 - 2790 Lime and Shale

CASING RECORD

Ran 6 joints new 8 5/8" OD casing.
256.03' pipe set at 268' K.B. Cemented
with 300 sacks Common, 2% gel and 2% cc.
Plug down at 9:15 PM, 6-18-84, by Howco.

Plugged.

Deviation Surveys: 1° at 1910'
1° at 2790'

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1984

CONSERVATION DIVISION
Wichita, Kansas