


15.151-20350-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 34 Twp. 29 Rge. 11W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
SW NE NE
Lease Owner Ronald Russ Prater Inc.
Lease Name Rolf Well No. # 1
Office Address 240 Rock Road, Suite 235, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Oil
Date Well completed January 22 1980
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced January 9 1980
Plugging completed January 22 1980
Reason for abandonment of well or producing formation _____
Depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wayne T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	301'	None
				4-1/2	2897'	1993.38'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 2675' and 4 sacks cement
Shot pipe at 2400, 2300, 2200, 2100 and 2000'
Pulled 50 joints 4 1/2" casing
Squeezed well with 4 sacks hulls, 25 sacks gel,
4 sacks hulls, 100 sacks 50/50 pozmix cement
with 4% added gel and 3% calcium chloride.

STATE RECEIVED
JAN 25 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold Box 698, Gt. Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1980

Guth L. Stoen
Notary Public.

My commission expires September 27, 1981



CONTRACTOR'S WELL LOG

OPERATOR: Ronald Russ Prater, Inc.
CONTRACTOR: Union Drilling Co., Inc.
WELL NAME: Rolf Unit #1
LOCATION: SW NE NE Section 34-29S-11W
Pratt County, Kansas
COMMENCED: September 12, 1976
COMPLETED: September 17, 1976

0	1065	Shale and shells	8-5/8" casing set at 301 w/275 sacks
1065	1919	Shale and shells	
1919	2260	Shale and lime	
2260	2945	Lime and shale	
2945		T. D.	

We certify that the above and foregoing is a true and correct copy of the log of the Rolf Unit #1, SW NE NE Section 34-29S-11W, Pratt County, Kansas.

UNION DRILLING CO., INC.

By *R. D. Messinger*
R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public in and for the afore-said county and state as of this 24th day of September, 1976.

Donna F. Brown
Donna F. Brown, Notary Public

My commission expires:

July 29, 1978

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1979
CONSERVATION DIVISION
Wichita, Kansas