

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-20,724 - 80-5D

LEASE NAME Miller C

WELL NUMBER 1-34

 Ft. from S Section Line

 Ft. from E Section Line

NW SE SW
 SEC. 34 TWP. 29S RGE. 11W (X) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 3-8-89

Plugging Completed 3-14-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS P.O. Box 158 Belpre, Ks. 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 13, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2800

Perfs: 2719-41 O.A. PBID 2760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	251	7"	251	0
		251	2793	4 1/2"		1782'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Dumped sand to 50' above top perfs, and dumped 5 sx. cement.

March 14, 1989: 400# hulls, 8 sx. ge., 40 sx. cement, 8 sx. gel, 100# hulls, plug, 82 sx. cement, Max. 1600#, SIP 1150#. 6% gel, 60 4 poz. mix.

(If additional description is necessary, use BACK of this form)
 RECEIVED
 STATE CORPORATION COMMISSION License No. 5893

Name of Plugging Contractor Pratt Well Service, Inc.

Address P.O. Box 847 Pratt, Kansas 67124 APR 7 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl 04-07-89


STATE OF Kansas COUNTY OF Pratt

CONSERVATION DIVISION
 Wichita, Kansas
 of plugging contractor
 XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX

Judy Berry (Employee of plugging contractor) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 5th day of April, 1989

Dorothy M. Furgason
 Notary Public
 My Commission Expires February 6, 1993

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - MILLER "C" #1-34
Location: NW SE SW, Section 34-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 1, 1980
COMPLETED: February 8, 1980

TOTAL DEPTH: 2800'

LOG

0 - 158 Clay and Sand
158 - 259 Shale and Gravel
259 - 459 Shale
459 - 1023 Lime and Shale
1023 - 1798 Shale
1798 - 2800 Lime and Shale

CASING RECORD

Ran 8 joints used 7" OD casing, 249.61'
set at 251.61' G.L. Cemented with 150
sacks 60/40 Pozmix with 2% gel and 3% cc.
Plug down at 11:15 AM, 2-1-80, by Howco.

Ran 85 joints 4 1/2" OD, 10.5# used
casing, 2792.81' pipe set at 2792.81'
G.L. Cemented with 75 sacks Regular Pozmix
#1 with 18% salt, 3/4 of 1% CFR-2, 10#
per sack gilsonite and 1/4# tuffiber.
Plug down at 3:00 AM, 2-8-80.

Deviation Surveys: 1° at 1798'
3/4° at 1991'
1 1/2° at 2800'