

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21426-00-00

LEASE NAME Rolf

WELL NUMBER 2-33

2010 Ft. from (S)N Line of Section (circle one)

1950 Ft. from (W)Line of Section (circle one)

SPOT LOCATION 30°N&30°W - OF C - NE - NW

SEC. 33 TWP. 29S S. RGE 11 (E) or (W)

COUNTY Pratt

Date Well Completed _____

Date Plugging Commenced November 26, 1997

Date Plugging Completed December 2, 1997

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE OPERATOR F. G. Holl Company, L.L.C.

ADDRESS 6427 E. Kellogg P.O. Bos 780167

CITY, STATE, ZIP Wichita, Kansas 672878-0167

PHONE# 316, 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 23, 1997 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation(s) Indian Cave Sand Depth to Top 2762' Bottom 2796' T.D. 2829'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Pipe	0'	257'	8 5/8"	257'	0'
	Casing	0'	2828'	4 1/2"	2828'	0'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

On November 26, set cast iron bridge plug at 2700' and shot 4 1/2 casing off at 2080' and pulled 2080' and dumped 2 sxs. of cement on top of the plug. On December 2, Halliburton pumped 300 lbs. of hulls, 10 sxs. of gel, 50 sxs. cement, 10 sxs. gel, 100 lbs. hulls, 8 5/8 wiper plug, 100 sxs. cement. 60/40 poz - 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl Company, L.L.C.

STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart of Pratt Well Service Inc. (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart

(Address) P. O. Box 847 Pratt, Kansas 67124

1997 DEC 22 2:12 PM
RECEIVED
KANSAS CORP COM
12-22-97

SUBSCRIBED AND SWORN TO before me this 18th day of December, 1997

Kenneth W. Furgason
Notary Public

My Commission Expires: 06/19/00

KENNETH W. FURGASON
Notary Public - State of Kansas
My Appl. Expires 06/19/00