

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,851-6D-60
 LEASE NAME Ford "A"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-14
1650' Ft. from S Section Line
2310' Ft. from E Section Line

LEASE OPERATOR F. G. Holl Company
 ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

SEC. 14 TWP. 29S RGE. 11W (E or W)
 COUNTY Pratt

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed 8-30-87

Character of Well D & A

Plugging Commenced 5:00 AM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6:30 AM

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	263' KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. 50 sacks at 1080'; 40 sacks at 300';
10 sacks at 40' and 15 sacks in rathole. Used 60/40 Pozmix,
6% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.


Richard L. Mead

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead
 Richard L. Mead, President

(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1987

Agnes D. Wurst, Notary Public
 My Commission Expires: 4-6-89

SEP 2 1987
 09-02-87
 CONSERVATION Form OCP-4
 Wichita, Kansas
 Revised: 07-86

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - FORD "A" 1-14

Located: SW NW SE, Section 14-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 21, 1987

COMPLETED: August 30, 1987

TOTAL DEPTH: 4750'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 40 Sand	Ran 6 joints 8 5/8" casing. 248' pipe set at 263' K.B. Cemented with 210 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 4:45 PM, 8-21-87, by Howco.
40 - 263 Clay, Shale	
263 - 890 Shale and Red Beds	
890 - 1033 Shale	
1033 - 1054 Anhydrite	
1054 - 4510 Lime and Shale	
4510 - 4625 Lime	
4625 - 4750 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 1920'
7/8° at 4650'

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1987

CONSERVATION DIVISION
Wichita, Kansas