

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

SEP 2 1982

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sedgwick SEC. 35 TWP. 27S RGE. 2 E/W
Location as in quarters or footage from lines:
SE NW NE

		*	
		35	

Locate Well
correctly on above
Section Platt.

Lease Owner Sabre Exploration, Inc.
Lease Name Hubbard Well No. #1
Office Address 120 S. Market, Suite 510, Wichita KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 7/22/82
Application for plugging filed 5/20/82
Plugging commenced 7/22/82
Plugging completed 7/22/82
Reason for abandonment of well or producing formation non-commercial

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation Mississippian Depth to top 3493' bottom T.D. 3545'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Mississippian	oil & wtr	3493	TD	4 1/2"	3540'	3119'
				8 5/8"	452'	none

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Ran bailer and dumped in sand to plug back, dumped 4 sacks cement with
dump bailer, shot pipe off at 3119', laid casing down. Bailed well
down, ran in 17 joints tubing @ 523', mixed 9 sx. gel and 3 sx. hulls
@ 523', spotted 60 sx. cement @ 523', 25 sx. @ 210', 25 sx. @ 60'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gressel Oil Field Service


STATE OF Kansas COUNTY OF Sedgwick, ss.
Matthew W. Totten (employee of owner) or owner or operator of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Matthew W. Totten
510 120 Bldg., Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 1982

Dorlee J. Kremer
Dorlee J. Kremer Notary Public.

Commission expires: 3/29/86



GENERAL TERMS AND CONDITIONS

All prices are exclusive of any Federal, State or Special Taxes for the sale or use of merchandise or service listed. The amount of taxes required to be paid by the seller shall be added to the quoted prices payable by the buyer.

Unless satisfactory credit has been established, cash payment will be required in advance.

We will make reasonable attempt to get to and from the well under our own power. Should we be unable to do so because of poor or inadequate road conditions, and it becomes necessary to employ a tractor or other pulling equipment, such equipment will be supplied by the customer, or if furnished by us, the cost will be charged to the customer.

We endeavor to design and maintain our equipment to safely service properly drilled and conditioned wells. We carry public liability and property damage insurance; but as there are so many uncertain and unknown conditions not subject to our control, we can neither be liable for injuries to property or persons nor for loss or damage arising from the performance of our services or resulting therefrom.

In the event equipment or tools are lost in rendering our services, the customer agrees to make reasonable attempt to recover same. If not recovered, customer agrees to reimburse us for their value.

If a material service is ordered and the customer cancels same after the solution has been prepared, a charge will be made to the customer for the expenses incurred.

Unless otherwise specified, a dead haul charge of \$1.25 per mile, one way, will be made for each service unit ordered but not used.

All prices are subject to change without notice.

All unpaid bills are subject to interest after 60 days from date of invoice.

DRILLERS LOG

API # - 15-173-20, 480-0000

OPERATOR: SABRE EXPLORATION, INC.
 510 One Twenty Bldg., 120 S. Market, Wichita, Kansas 67202
 CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Hubbard Well No. 1
 Sec. 35 T. 27S R. 2W Spot SE NW NE
 County Sedgwick State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 452' with 350 Sxs. 3% CC

Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Well Total Depth 3546'

Drilling Commenced: 3/23/82 Drilling Completed 4/3/82

Formation	From	To	Tops
Cellar	0	7	Kansas City - 2955
Shale, Lime	7	1710	Mississippi - 3540
Shale	1710	1831	
Lime, Shale	1831	2565	
Shale	2565	2709	
Lime, Shale	2709	2955	
Lime	2955	3028	
Lime, Shale	3028	3540	
Lime	3540	3546	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 21 1982
 CONSERVATION DIVISION
 Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____ Type and Depths Covered _____

