

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

SEDGWICK County. Sec. 35 Twp. 27 Rge. 2W &W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
N 8 E SE NE

Lease Owner Carr Explorations, Inc.
Lease Name HUBBARD Well No. 1

Office Address 1540 N. Broadway - Wichita, KS 67214
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above
Section Plat

Date Well completed July 1977
Application for plugging filed 12-20 1977
Application for plugging approved 12-20 1977
Plugging commenced 12-19 1977
Plugging completed 12-27 1977

Reason for abandonment of well or producing formation
Non Commercial

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Mississippi Depth to top 3502 Bottom 3510 Total Depth of Well 3570
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Water, 550	3502	3510	4 1/2	3569	2539

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Bottom Bridge at 475' Fill W/25 SX Cement
Fill to 45' W/Rock, 45'- Surface Filled W/15 SX

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & S Well Service

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Gary E. Caruthers (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1540 N. Broadway - Wichita, KS 67214
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1978

Loretta A. Keith
Loretta A. Keith Notary Public.

My ~~XXXXXX~~ expires 10/5/81
Appointment



Hubbard completion file

DRILLERS LOG

OPERATOR: Carr Explorations, Inc.; 1540 North Broadway; Wichita, KS 67214

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Hubbard Well No. 1

Sec. 35 T. 27S R. 2W Spot app. NE SE NE

County Sedgwick State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 460' with 300 Sxs.

Production: 4 1/2" @ 3568' with 100 Sxs.

Type Well: Oil Total Depth 3570' K.B.

Drilling Commenced: 7-21-77 Drilling Completed 7-28-77

Formation	From	To	Tops
Cellar	0	7	Kansas City 2899
Shale & Lime (Stks)	7	365	Mississippi 3490
Shale	365	410	
Lime	410	460	
Shale & Lime	460	615	
Shale	615	1130	
Shale & Lime	1130	2375	
Shale	2375	2505	
Lime & Shale	2505	2730	
Lime	2730	2885	
Shale	2885	2899	
Lime	2899	3100	
Shale & Lime	3100	3490	
Lime	3490	3570	

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1977
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size From To

Cementing Record: Sacks

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production:

Electric Log Type and Depths Covered