

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-21909-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 5-13S-17W
2360 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HEROLD Well #: 1
County: ELLIS Total Vertical Depth: 3612 feet

Operator License No.: 3444
Op Name: KARLIN, GENE DBA GENE KARLIN CO.
Address: 1111 OAKMONT ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3597		250 SX
SURF	8.625	248		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2015 9:30 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: BRIAN KARLIN Company: GENE KARLIN CO Phone: (785) 623-3290

Proposed Plugging Method: Ordered 315 sx 60/40 pozmix 4% gel cement, 500 # hulls.
DV Tool at 1304' w/550 sx cement.
Casing leaks at 1494' - 1788'
Perforations: 3365' - 3370', 3394' - 3396', 3411" - 3414', 3475' - 3480', 3503' - 3507', 3594' - 3600'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2015 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ultimate Well Service ran in hole with tubing to 3300' and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 1850' and pumped 125 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 20 sx cement with 300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface casing and pumped 5 sx cement w/300 psi. Shut in pressure 300 psi.

GPS: 38.95030 -099.23204

Perfs:

Top	Bot	Thru	Comments
3594	3600		
3503	3507		
3475	3480		
3411	3414		
3394	3396		
3365	3370		

Remarks: QUALITY CEMENTING CO TICKET # 1283

Plugged through: TBG

7/29/15 CKM

District: 04

Signed _____



(TECHNICIAN)

CKM

KCC WICHITA

Form CP-2/3

JUL 09 2015

JUL 14 2015

RECEIVED