

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-01525-00-01
Spot: NESWNE Sec/Twnshp/Rge: 14-9S-22W
3622 feet from S Section Line, 1761 feet from E Section Line
Lease Name: VAN LOENEN Well #: 4
County: GRAHAM Total Vertical Depth: 3828 feet

Operator License No.: 31434
Op Name: L & J OIL PROPERTIES, INC.
Address: 1700 N WATERFRONT PKWY BLDG 30
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3825		150 SX
SURF	8.625	214		150 SX

Well Type: EOR UIC Docket No: E10328.2 Date/Time to Plug: 07/14/2015 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: SHANE MADDOX Company: SCOTT SERVICES Phone: (785) 737-7139

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 3491' - 3680'.
Alt II is complete

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2015 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3476' and pumped 50 sx neat cement followed by 50 sx cement w/200 # hulls.
Pulled tubing to 2827' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2015' and
pumped 100 sx cement w/100 # hulls. Pulled tubing to 1020' and pumped 100 sx cement.
Good circulation of cement. Pulled tubing out. Tied on and squeezed w/20 sx cement. Shut in
pressure 500 psi. Tied on to backside and squeezed w/10 sx cement. Shut in pressure 200 psi.

GPS: 39.27325 -099.74086

Perfs:

Top	Bot	Thru	Comments
3491	3680		

Remarks: QUALITY CEMENT TICKET # 1169

Plugged through: TBG

7/29/15 ckm

District: 04

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

JUL 14 2015

JUL 17 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

uicv