

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-22052-00-00  
Spot: NENENWNW Sec/Twnshp/Rge: 6-34S-13E  
5150 feet from S Section Line, 4234 feet from E Section Line  
Lease Name: TOWER Well #: SWD-1  
County: CHAUTAUQUA Total Vertical Depth: 2226 feet

Operator License No.: 34458  
Op Name: LONG AND WARE OIL, A GENERAL PA  
Address: 2200 LYNN AVE.  
PAWHUSKA, OK 74056

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2226		0 SX
SURF	8.625	40		0 SX
SURF		92		

Well Type: SWD UIC Docket No: D20550.0 Date/Time to Plug: 07/01/2015 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: LONG AND WARE OIL Company: Phone: (918) 698-7282

Proposed Plugging Method: run 1" to 600', cement to surface, pull 1" out, top off with cement, then tie onto top and do a squeeze job.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/01/2015 12:00 PM KCC Agent: DUANE SIMS


Actual Plugging Report:  
On February 23, 2015 contractor ran 2" tubing to 1630' and hit solid. They circulated 105 sacks of cement and pulled 2". They tried to make disposal well in different zone but cement bond log would not allow this. Well was perforated at 570'. On July 1, 2015 contractor ran 1" to 600' and circulated 87 sacks of cement to surface. Pulled 1" and topped well off. Hooked onto casing and tried to squeeze casing. Well pressured up to 1000 psi. Well was shut in. A total of 192 sacks of cement were used to plug this well.

Perfs:  
  
RECEIVED  
KCC DIST # 3  
JUL 09 2015  
CHANUTE, KS  
  
DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed  7/29/15 okm  
(TECHNICIAN)

KCC WIC Form CP-2/3  
JUL 16 2015 7-16-15  
RECEIVED uic