

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21593-00-00  
Spot: SESE Sec/Twnshp/Rge: 2-27S-18W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HANEY 'A' GAS UNIT Well #: 1-2  
County: KIOWA Total Vertical Depth: 4720 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 9342 E CENTRAL  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	4.5	4722	2268	WITH 125 SX CMT
SURF	8.625	346		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2015 9:30 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (316) 636-2737

Proposed Plugging Method: CIBP @ 4620' WITH 2 SX CMT OR SAND TO 4620' WITH 5 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2015 11:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4620' WITH 2 SX CMT. 1ST PLUG AT 1078' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 398' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4690	4696		
4682	4690		
4674	4696		


Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

7/29/15 *SCM*

District: 01

Signed  (TECHNICIAN)

RECEIVED  
JUL - 7 2015  
KCC DODGE CITY 

Received  
KANSAS CORPORATION COMMISSION

JUL 10 2015

CONSERVATION DIVISION  
WICHITA, KS