

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21637-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 1-27S-18W
660 feet from S Section Line, 990 feet from W Section Line
Lease Name: HANEY 'B' Well #: 1-1
County: KIOWA Total Vertical Depth: 4735 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4630		2sx
PROD	4.5	4734	2522	150 SX
SURF	8.625	312		250 SX
TI	2.375	4701		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/09/2015 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (620) 532-9232

Proposed Plugging Method: Set CIBP @ 4630' w/ 2sx cement. 1st plug @ 1090' w/ 15sx gel, 50sx cement. 2nd plug @ 350' w/ 50sx cement. 3rd plug @ 40' w/ 20sx cement.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/09/2015 9:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Set CIBP @ 4620' w/ 2sx cement. 1st plug @ 1089' w/ 15sx gel, 50sx cement. 2nd plug @ 365' w/ 50sx cement. 3rd plug @ 40' w/ 20sx cement to 0'.

Perfs:

Top	Bot	Thru	Comments
4700	4712		MISSISSIPPIAN
4684	4712		MISSISSIPPIAN

Remarks: 60/40 POZMIX 4% GEL BY HURRICANE SERVICES, INC.

Plugged through: CSG

7/29/15 ckm

District: 01

Signed [Signature]

RECEIVED
JUL 17 2015
KCC DODGE CITY

JA

(TECHNICIAN)
KCC WICHITA

JUL 24 2015
RECEIVED