

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21705-00-00  
Spot: N2N2NWSE Sec/Twnshp/Rge: 5-29S-19W  
2530 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: HAYSE 'B' Well #: 1-5  
County: KIOWA Total Vertical Depth: 5035 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 9342 E CENTRAL  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	4960		2sx
PROD	4.5	5015	2676	125 SX
SURF	8.625	610		220 SX
T1	2.375	5021		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/13/2015 11:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (620) 562-9232

Proposed Plugging Method: Set CIBP @ 4960' w/ 2sx cement. 1st plug @ 1328' w/ 15sx gel, 50sx cement. 2nd plug @ 660' w/ 50sx cement. 3rd plug @ 40' w/ 20sx cement

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/13/2015 1:55 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Set CIBP @ 4960' w/ 2sx cement. 1st plug @ 1327' w/ 15sx gel, 50sx cement. 2nd plug @ 644' w/ 50sx cement, 3rd plug @ 40' w/ 35sx cement to 0'.

Perfs:

Top	Bot	Thru	Comments
5015	5035		


Remarks: 60/40 POZMIX, 4% GEL BY HURRICANE SERVICES, INC

Plugged through: CSG

5/29/15 CRM

District: 01

Signed



(TECHNICIAN)

RECEIVED

JUL 17 2015

KCC DODGE CITY

KCC WICHITA

JUL 24 2015

RECEIVED