

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22885-01-00
Spot: S2S2SESW Sec/Twnshp/Rge: 9-11S-22W
75 feet from S Section Line, 1980 feet from W Section Line
Lease Name: SCHLEGEL 9 Well #: #3H
County: TREGO Total Vertical Depth: 3400 feet

Operator License No.: 9810
Op Name: MCELVAIN ENERGY, INC.
Address: 1050 17TH ST STE 2500
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		
PROD	7	4520		650 SX
SURF	9.625	320		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2015 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: _____ Company: PROFESSIONAL PULLING SERVIC Phone: (78) 548-3672

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 28 sx gel.
CIBP at 3400'.
Casing circulated with cement for Alt II
TVD-3400'
MTV-7000'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2015 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3400' and pumped 21 sx gel followed by 75 sx cement. Pulled tubing to 1700' and pumped 7 sx gel followed by 150 sx cement. Pulled tubing to 400'. Circulated cement w/65 sx cement. Pulled tubing and topped off casing with 50 sx cement. Tied on to backside and squeezed w/20 sx cement. Shut in pressure 400 psi.


GPS: 39.10315 -099.77046

Remarks: ALLIED CEMENTING TICKET # 055666

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

7/29/15 ckm

cm

JUL 06 2015

KCC WICHITA

Form CP-2/3

JUL 14 2015

RECEIVED