

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23643-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 14-25S-14W  
4597 feet from S Section Line, 4532 feet from E Section Line  
Lease Name: HE TANNER Well #: 1  
County: STAFFORD Total Vertical Depth: 4365 feet

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S BROADWAY STE 360  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3770		WITH 2 SX CMT
PROD	5.5	4345	1202	WITH 150 SX CMT
SURF	8.625	309		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2015 11:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JEFFREY A. BURK Company: MID-CONTINENT ENERGY Phone: (316) 250-5655

Proposed Plugging Method: SET CIBP @ 3770' WITH 2 SX CMT. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2015 1:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3770' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 908' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3824	3828		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL - 2 2015  
KCC DODGE CITY

JA

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 10 2015

CONSERVATION DIVISION  
WICHITA, KS