

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21943-00-00
Spot: NENW Sec/Twnshp/Rge: 36-15S-15W
4620 feet from S Section Line, 3630 feet from E Section Line
Lease Name: COTTEN Well #: 1
County: RUSSELL Total Vertical Depth: 3435 feet

Operator License No.: 3134 •
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3434		100 SX
SURF	8.625	260		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2015 9:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: G L M Phone: (785) 639-5415

Proposed	07/06/2015- Ordered 350 sx 60/40 pozmix 4% gel cement and 600 # hulls.
Plugging	07/07/2015- Ordered 300 sx 60/40 pozmix 4% gel cement.
Method:	Junk in hole at 780'. Worked on getting hole cleaned out for two days with no results.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2015 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

07/06/2015- Perforations at 250'. Ran tubing to 585' and pumped 100 sx cement w/50 # hulls. Backside on a slight vacuum. Pulled tubing to 430'. WOC. Ran tubing back down and pumped 150 sx cement w/250 # hulls. Had slight return but on vacuum after shutting down pump truck. POOH and shut down for the night.
07/07/2015- Ran tubing and tagged at 450'. Pumped 60 sx cement. Cement circulated out of backside. POOH. Hooked to casing and pumped an additional 60 sx cement. Circulated cement out of the braden head. Casing and cellar were full.
07/08/2015- Checked on fill up.
GPS: 38.70955 -098.94367

Perfs:

Top	Bot	Thru	Comments
3378	3382		
3158	3161		

Remarks: GLOBEL CEMENTING COMPANY TICKET # 1729 AND 1706

Plugged through: TBG

7/29/15 CKM

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CM

JUL 09 2015

Received
KANSAS CORPORATION COMMISSION
JUL 17 2015
CONSERVATION DIVISION
WICHITA, KS