

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21028-00-00
Spot: SENWSW Sec/Twnshp/Rge: 21-23S-10W
1614 feet from S Section Line, 4422 feet from E Section Line
Lease Name: KREIE D Well #: 6
County: RENO Total Vertical Depth: 4006 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3785		200 SX
SURF	8.625	215		165 SX

Well Type: SWD UIC Docket No: D23908.0 Date/Time to Plug: 06/25/2015 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: KIRK GLENN Company: Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/25/2015 1:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3736' CAPPED WITH 2 SX CEMENT ON TOP. PERFORATED CASING @ 1460' & 900' & 275'. TRIPPED TUBING INTO 1460' SPOTTED 35 SX OF CEMENT (CLASS A W/3% CC), TRIPPED TUBING TO 900' SPOTTED 35 SX CEMENT. TRIPPED TUBING TO 275' CIRCULATED TO SURFACE WITH 105 SX OF CEMENT. TTO, CEMENT FELL INSIDE CASING, TOPPED WITH 125 SX CEMENT, FELL AGAIN. WAITED 2.5 HOURS TAGGED CEMENT @ 1280'. TRIPPED TUBING BACK INTO 900', PUMPED 50 SX CEMENT PRESSURED UP TO 300 LB, TRIPPED TUBING OUT TO 275' CIRCULATED TO SURFACE WITH 45 SX OF CEMENT. CAME BACK AND CUT HEAD OFF AND TOPPED WITH 15 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3707	3708		
3695	3699		
3631	3633		
3395	3399		

Remarks: BASIC ENERGY PROVIDED CEMENT FOR PLUGGING. PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

KCC WICHITA

JUL 14 2015

RECEIVED

✓

UIC