

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25863-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 25-16S-25W
1001 feet from N Section Line, 1689 feet from E Section Line
Lease Name: JON-MAXINE TRUST Well #: 1
County: NESS Total Vertical Depth: 4635 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	150sx cement

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/13/2015 5:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1st plug @ 1940' w/ 50sx cement, 2nd plug @ 1150' w/ 80sx cement, 3rd plug @ 550' w/50sx cement, 4th plug @ 250' w/ 50sx cement, 5th plug 60' w/ 20sx cement, 6th plug 30sx in rat hole

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: NONE
Date/Time Plugging Completed: 07/13/2015 5:00 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

1st plug @ 1940' w/ 50sx cement, 2nd plug @ 1150' w/ 80sx cement, 3rd plug @ 550' w/ 50sx cement, 4th plug @ 250' w/ 50sx cement, 5th plug @ 60' w/ 20sx cement, 6th plug rat hole w/ 30sx cement

Perfs:

Remarks: CEMENT: 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL CEMENTING

Plugged through: DP

District: 01

Signed

Robert Dickerson

(TECHNICIAN)

SA

7/29/15 CEM

RECEIVED

JUL 13 2015 *KMS*

KCC DODGE CITY

KCC WICHITA

JUL 24 2015

RECEIVED