

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-26363-00-00  
Spot: NWSWNESE Sec/Twnshp/Rge: 20-32S-9E  
1881 feet from S Section Line, 1110 feet from E Section Line  
Lease Name: VAUGHN Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 1475 feet

Operator License No.: 4699  
Op Name: PHILLIPS OIL PROPERTIES INC.  
Address: 733 N. BALTIMORE  
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1474		200 SX
SURF	8.625	46		25 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2015 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: TROY A. PHILLIPS Company: \_\_\_\_\_ Phone: (316) 295-4335

Proposed Plugging Method: Sand and cement plug to 1414'. Surface plug 550' to surface. Have cement Bond Log showing 4-1/2" casing cemented to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/19/2015 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:  
Ran 1" to 1425' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 75 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1441	1448		
1431	1436		

RECEIVED  
KCC DIST # 3  
JUL 14 2015  
CHANUTE, KS  
DS

Remarks:

Plugged through: TBG

District: 03 Signed Duane A. Sims (TECHNICIAN) 7/29/15 crm

KCC WICHITA  
JUL 16 2015  
RECEIVED