

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22175-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 26-31S-9E
687 feet from S Section Line, 2989 feet from E Section Line
Lease Name: HEINZ Well #: A-1
County: ELK Total Vertical Depth: 2320 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 733 N. BALTIMORE
DERBY, KS 67037

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1543		110 SX
SURF	7.625	40		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2015 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TROY A. PHILLIPS Company: _____ Phone: (316) 295-4335

Proposed Plugging Method: Sand and cement plug to 1450'. Perf 550' and circulate cement to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2015 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 550'. Ran 1" to 1500' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 5 sack plug. Pulled up to 550' and circulated cement inside and outside casing to surface. Pulled 1" and topped well off. A total of 110 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JUL 14 2015
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

Form CP-2/3

JUL 16 2015

RECEIVED

7/29/15. CXM