

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-00182-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 14-23S-16W
4950 feet from S Section Line, 2333 feet from E Section Line
Lease Name: KASSELMAN (OWWO) Well #: 1
County: PAWNEE Total Vertical Depth: 4188 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4185		125 SX
SURF	8.625	220		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/02/2015 10:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: PINTAIL PETROLEUM, LTD. Phone: (785) 798-3641

Proposed Pumping Method: Pump 20sx cement w/ 100-200# hulls @ 3950'. 1st plug @ 1040' w/ 10sx gel, 50sx cement, 2nd plug @ 450' w/ 50sx cement, 3rd plug @ 270' w/ 50sx cement, 4th plug @ 40' w/ 20sx cement

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/02/2015 2:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Could only get 1" of stretch. No record of squeezes. Pumped bottom w/ 20sx cement w/ 100# hulls @ 3962'. Ran CBL and showed intermittent cement from 1040'-270'. 1st plug perforated @ 1040' w/ 50sx cement and 50# hulls, 2nd plug perforated @ 250' and circulated cement to surface with 95sx cement. Ran tubing out of hole and topped off with 15sx cement

Pulled off

Perfs:

Top	Bot	Thru	Comments
4038	4044		
3999	4004		

Remarks: 60/40 POZMIX 4% GEL BY SWIFT SERVICES, INC.

Plugged through: TBG

7/29/15 ECM

District: 01

Signed *[Signature]*
(TECHNICIAN)

RECEIVED
JUL 17 2015
KCC DODGE CITY

SA

KCC WICHITA
JUL 24 2015
RECEIVED