

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26600-00-00
Spot: E2W2NESW Sec/Twnshp/Rge: 22-27S-18E
2017 feet from S Section Line, 1848 feet from W Section Line
Lease Name: BEACHNER BROS Well #: 22-27-18-1
County: NEOSHO Total Vertical Depth: 1034 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1029		124 SX
SURF	8.625	21		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/09/2015 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2015 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to 1030 ft. 70 sacks of cement were then pumped. The cement string was pulled to 500 ft and 30 sacks of cement were pumped. The cement string was pulled to 250 ft and 14 sacks of cement pumped. The cement string was removed and the well topped off with 6 sacks of cement. A total of 120 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
937	940		
636	638		
601	604		
597	601		
584	586		
507	511		

RECEIVED
KCC DIST #3
JUL 24 2015
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

KCC WICHITA

JUL 29 2015

7/29/15 crm RECEIVED