

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27287-00-00
Spot: W2NESW Sec/Twnshp/Rge: 22-27S-18E
1978 feet from S Section Line, 1776 feet from W Section Line
Lease Name: BEACHNER BROTHERS Well #: C22-27-18-1
County: NEOSHO Total Vertical Depth: 1037 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1025		120 SX
SURF	8.625	23		20 SX
T1	2.375	832		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/09/2015 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 03/10/2015 11:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to 1030 ft. 70 sacks of cement with cottonseed hulls were then pumped. The cement string was pulled to 500 ft and 32 sacks of cement pumped. The cement string was pulled to 200 ft and 10 sacks of cement pumped. The cement string was removed and the well topped off with 6 sacks. A total of 118 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
803	805		

RECEIVED
KCC DIST # 3
JUL 24 2015
CHANUTE, KS
AD
KCC WICHITA
JUL 29 2015

Remarks:

Plugged through: CSG

7/29/15 CKM

District: 03

Signed Alan by. Dunning
(TECHNICIAN)