

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27389-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 28-27S-18E
458 feet from N Section Line, 984 feet from E Section Line
Lease Name: BEACHNER BROTHERS Well #: C28-27-18-2A
County: NEOSHO Total Vertical Depth: 1058 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1036		130 SX
SURF	8.625	23		5 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 02/06/2015 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 02/06/2015 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to 1023 ft. 58 sacks of cement were then pumped. The cement string was pulled to 500 ft and 28 sacks of cement pumped. The cement string was removed and the well topped off with 12 sacks of cement. A total of 98 sacks of portland cement were used to plug well.

Perfs: **KCC WICHITA**
JUL 29 2015
RECEIVED

RECEIVED
KCC DIST # 3
JUL 24 2015
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

7/29/15cm