

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22211-00-00
Spot: SESEW Sec/Twnshp/Rge: 36-23S-5E
330 feet from S Section Line, 3300 feet from E Section Line
Lease Name: JANZEN B Well #: 4
County: BUTLER Total Vertical Depth: 2603 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2603		100 SX
SURF	8.625	208		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL COMPANY Phone: (620) 222-4304

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/30/2015 1:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET AT 2450' AND CAPPED W/4 SKS OF 60/40 4% CEMENT. 2) TUBING RAN IN TO 935', SPOTTED 35 SKS CEMENT. 3) CASING PERFORATED AT 260'. PUMPED 115 SKS OF CEMENT, CIRCUALTED TO SURFACE. 4) CUT CASING HEAD OFF AND TOPPED OFF W/4 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2491	2509		CSG

KCC WICHITA
JUL 29 2015
RECEIVED

Remarks: CEMENTING COMPLETED BY QUALITY WELL SERVICE, ELLINWOOD, KS. TICKET #6011. PLUGGED DUE TO DENIED TA/ HIGH FLUID LEVEL.

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

7/29/15 CPM